BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/09/2016-17 Dated: 30-03-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 10

Name of Work:-Providing Temporary Immersion Tank for lord Ganesh Idols at near Yelahanka lake in ward No:1 &2 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G Muniraju (KBS Engineering Works)	
				Rate	Rate in Words
1	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1) PWD SR 2016-17	cum	221.00	166.00	Rupees one hundred sixty six only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1))	cum	221.00	100.00	Rupees one hundred only
3	Code 0516-Providing Plastic Sheet (Page No xxvi/ I.768 PWD SR 2016-17	Sqm	778.00	6.00	Rupees six six
4	Engaging Unskilled heavy Mazdoor labour for guarding and for helping the public to immersion tank Ganesh idols and to safe guard the public duging the pooja Time (including Expert swimmers) Page No LIV Sl No 5 SR 2016-17	days	117.00	258.00	Rupees two hundred fifty eight only
5	1031 - Hire charges of Water Tanker/Day (P.No.XXXXVI/ Code No.1032 Sl.No.24 PWD SR 2016-17)	Each	50.00	485.00	Rupees four hundred eighty five only
6	Providing stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No 50 Code 400 metal Component PWD SR page No II SR 2016-17	Cum	45.00	795.00	Rupees seven hundred ninety five only
7	Hire Charges for two Tier Barricading with casurens poles at 2.50mtrs C/C vertically and 1.50 mtrs C/C Horizontaly with Necessary earth work and labour (steel baricading)	Sft	5850.00	10.00	Rupees ten only
8	Hire charge for Armless Plastic Chairs	Nos	900.00	3.90	Rupees three and paise ninety only
9	Hire charge for wooden Table of size 6ft x2ft	Nos	180.00	15.00	Rupees fifteen only only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri G Muniraju (KBS Engineering Works)	
				Rate	Rate in Words
10	Hire charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD SR 2010-11 P.55/I.6 IIIb)	Mtrs	2871.00	9.00	Rupees nine only
11	1321 Hire charge of 100 KVA generator including operator, Fuel transportation and Handling charges (PWD SR 2013-14(PXXXX /I.92) code No 132	Hrs	72.00	495.00	Rupees four hundred ninety five only
12	Hire Charges for Shamiyana side wall of 8ft hight (Size 15ftx20ft=300sqft)	Rft	2700.00	2.00	Rupees two only
13	Hire charge for Shamiyana with Necessary Bambo Poles Erection Charges Including transportation (Size 15ftx20ft=300sqft)	Sft	2700.00	5.00	Rupees five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.